



# Overview of the New Radioactive Ion Beam Accelerator Complex RAON in Korea

**Byungsik Hong** 

Center for Extreme Nuclear Matters (CENuM), Korea University

for Rare Isotope Science Project (RISP), IBS





#### **Outline**

- **1. Overview of RISP**
- 2. Accelerator system
- 3. RI & experimental systems
- 4. Status of beam commissioning and summary





#### **Overview of RISP**



#### **CAON** Overview of Rare Isotope Science Project (RISP)



- Goal: To build a heavy-ion accelerator complex RAON for rare isotope science research
  - RAON: Rare isotope Accelerator complex for ON-line experiments
- Budget: Total KRW 1,518 B (~U\$ 1.2 B for 1 U\$=KRW 1,300) for phase I
  - Accelerator & experimental facilities: ~U\$ 400 M
  - Civil engineering & conventional facilities: ~U\$ 800 M, including ~U\$ 270 M for purchasing land
- Project period: 2011-2022 (1<sup>st</sup> phase), 2023-2029 (2<sup>nd</sup> phase for high-energy Linac)

#### System installation project

Development, installation, and commissioning of the accelerator systems that provides the highenergy (200 MeV/u) and high-power (400 kW) heavy-ion beams



#### Facility construction project

Construction of the research and supporting facility to ensure the stable operation of the heavy-ion accelerator, experimental systems, and to establish a comfortable research environment in Korea



● Providing high-quality RI beams by ISOL & IF

ISOL: direct fission of <sup>238</sup>U by 70 MeV proton beams IF: 200 MeV/u <sup>238</sup>U (intensity: 8.3 pμA)

Providing high-intensity neutron-rich beams

For example,  $^{132}\text{Sn}$  with energy up to 250 MeV/u and intensity up to  $10^9$  particles per second

#### Providing more exotic RI beams

Combination of ISOL and IF

## RAON Layout





5

#### **RAON** Scientific goals



#### RAON

Accelerator complex ISOL + In-Flight Fragmentation

#### **Origin of Matter**

- Nuclear Astrophysics
- Nuclear Matter
- Super Heavy Element Search
- High-precision Mass Measurement

#### **Properties of Exotic Nuclei**

- Nuclear Structure
- Electric Dipole Moment and Symmetry
- Nuclear Theory
- Hyperfine Structure Study

#### **Applied Science**

- Bio-Medical Science
- Material Science
- Neutron Science

13 October 2022

#### **RIB** production methods at RAON





NP Semmar, Umv. of Warsaw

### **RAON** Expected RIBs from RAON





RAON is going to eventually combine ISOL and IF to provide more exotic RIBs.

RAON is expected to access to more neutron-rich regions of the nuclear chart.





#### **Accelerator system**



#### **RAON** Accelerator system (Overview)



- Installation and beam commissioning of the injector, SCL3 and ISOL
- Installation and machine commissioning of all experimental systems & IF separator

#### ● Phase II (~2029)

R&D, construction, installation and beam commissioning of SCL2

#### **CAON** Accelerator system (Overview of SC Linacs)



SCL3 (Phase I)

SCL2 (Phase II)



## **RAON** Injector system

- Two ECR IS's
  - 14.5 GHz ECR ion source
  - 28 GHz superconducting ECR ion source
- LEBT (E = 10 keV/u)
  - 10 keV/u, Dual bending magnet
  - Chopper & Electrostatic quads, Instrumentation
- RFQ (*E* = 500 keV/u)
  - 81.25 MHz, Transmission efficiency ~98%
  - CW RF power 94 kW (SSPA: 150 kW)
- MEBT (E = 500 keV/u)
  - Four RF bunchers (SSPA: 20, 15, 2 X (4 kW))
  - Simple quadrupole magnets, Instrumentation

#### Beam commissioning since Oct. 2020





### **RAON** Injector beam commissioning



Parameter	Value	Cavity RE power: 51.5 kW	LEBT Beam emittance	LEBT orbit correction
[Beam Properties]		(Design ~ 39.1 kW)	(Allison scanner)	
Frequency	81.25 MHz		73000	3
Particle	H <sup>1+</sup> to <sup>238</sup> U <sup>33+</sup>		50000	2
Input energy	10 keV/u			
Input current	0.4 mA		0.02	
Input emittance	0.012 cm·mrad		0.01	
Output energy	0.507 MeV/u			-1
Output emittance	0.0125 cm · mrad		$-0.01$ $2\pi = 0.233440$ emit n= 0.0584 alpha= 0.433	-2
Transmission	~98% (simulation)		-0.02 beta= 850.5	_3
Duty factor	100%		$\begin{array}{cccccccccccccccccccccccccccccccccccc$	∞ −4 −2 0 2 4 x [mm]

#### • Beams

- Ar<sup>9+</sup> (~30 μA) & Ar<sup>8+</sup> (~47 μA): 100 μs long pulsed beam
- Repetition rate: 1 Hz
- EPICS basis control system
- RFQ transmission
  - Measured by ACCTs in LEBT & MEBT (Error bar: 3σ)
  - Ar<sup>9+</sup> (91.9% w/ σ=1.9%) & Ar<sup>8+</sup> (95.4% w/ σ=1.3%)
- Energy
  - 507 keV/u by ToF using the two BPMs in MEBT



#### **RAON** SRF test facility and QC



- Processing the performance tests of SCL2 and SCL3 cavities & modules at cryogenic temperature
- Onsite test facility: 3 vertical test (VT) pits with 3 cavities per pit and 3 horizontal test (HT) bunkers
- It can cover all RAON cavities: QWR (81.25 MHz), HWR (162.5 MHz) and SSR1/SSR2 (325 MHz)







## **RAON SCL3 and cryoplants**

- Cryomodules (CM) & warm sections were assembled in the clean booth in the tunnel.
- Total counts of particles for the size > 0.5 μm/10 min. were less than 30.



- Cryoplants
  - SCL3 (4.2 kW @ 4.5 K), SCL2 (13.5 kW @ 4.5 K)
  - Two plants combined through the distribution box.
    If one plant down, the other can be maintained cold.
    (We operate either SCL2 & 3 together or just one.)



Commissioning ongoing



# Part 3.

**RI & experimental systems** 



#### **RAON** Overview of experimental systems



#### **RAON** ISOL system















Post Linac (Charge state n+)

- Driver beam: p,  $35 \le K \le 70$  MeV with  $\gtrsim 50$  kW
- Target: SiC, BN, UC<sub>x</sub>, MgO, etc. (CaO, BeO later)
- Ion Source: Surface, RILIS, Plasma

- RIB:  $6 \le A \le 250$ ,  $10 \le K \le 80$  keV,  $10^8$  pps (Sn), Purity > 90% @ Exp.
- Incident to RFQ with 10 keV/u
- Full remote maintenance system with TIS modularization



**ISOL** beamlines including subsystems were commissioned with Cs ions in 2021 (next slide).

#### **RAON ISOL SIB commissioning**



### **RAON ISOL SIB commissioning**



## **RAON** Cyclotron

- Specifications
  - Proton beams at 35~70 MeV
  - Maximum beam current: 0.75 mA
  - Two beamlines to the ISOL TIS bunker



- Jun. 2019: Contract with IBA
- Apr. 2020: Design finalized
- Jun. 2021: Factory Acceptance Test (FAT)
- Aug. 2021: Shipping
- Nov. 2021~Apr. 2022: Installation
- Oct. 2022: Site Acceptance Test (SAT) (plan)
- Still need to finalize the interface between cyclotron and ISOL



Cyclotron

#### Cyclotron beamline installation



- Korea Broad acceptance Recoil spectrometer & Apparatus
- Instrument for nuclear structure and nuclear astrophysics using stable or RI beams in the energy range of 1~40 MeV/u
  - Stable ions up to ~40 MeV/u from ECR IS ( $\leq$  40 MeV/u for  $A \leq$  40 and  $\leq$  20 MeV/u for  $A \geq$  100)
  - RIB production at a few MeV/u using the stable ion beams from ECR IS
  - Role of the recoil mass separator for RIBs from ISOL at beam energies less than a few MeV/u













**SNACK:** Silicon detector array for Nuclear AstrophysiCs study at KoBRA



13 October 2022

NP Seminar, Univ. of Warsaw

RISY



The momentum dispersion and resolving power at F1/F2/F3 agree with the expectation!

NP Seminar, Univ. of Warsaw

### RAON NDPS

Beam species

Beam energy

Beam current

**Bunch** length

Flight length

Neutron flux

**Repetition** rate

Maximum

Maximum

Target

- Nuclear Data Production System
  - d+C for white neutrons
    - n intensity at the end of the collimator  $\simeq 10^8$  neutrons/cm<sup>2</sup>/sec for 10 pµA
  - p+Li for monoenergetic neutrons

 $\sim 10 \ \mu A$ 

- n intensity at the end of the collimator  $\simeq 10^5~neutrons/cm^2/sec$  for  $10~p\mu A$ 

proton, deuteron

83 MeV for proton

C for white neutron

 $\sim 10^8 \, \text{cm}^{-2} \, \text{sec}^{-1}$  at 5 m

 $\sim 1 \text{ ns}$  (FWHM)

1 – 200 kHz

5 – 40 m

Li for monoenergetic neutron

49 MeV/u for deuteron



#### **RAON NDPS**

#### October 2020



#### July 2022



13 October 2022

NP Seminar, Univ. of Warsaw

### RAON LAMPS



- Large Acceptance Multi-Purpose Spectrometer
  - Beam energies up to 250 MeV/u for <sup>132</sup>Sn with an intensity as large as 10<sup>8</sup> pps
  - Comprehensive detector system to investigate the nuclear equation of state (EoS) and symmetry energy
  - All detector components and magnet were already developed, manufactured, and assembled.
  - Integration and commissioning of the whole LAMPS system is being planned at the end of 2022.



#### **CAON** TPC: Performance test with prototype





#### **RAON TPC: Construction of real detector**





### **CAON** TPC: Drift velocity measurement by cosmic ray



- Cosmic muon trigger
  - Coincidence of two scintillators (scintillator size: 20 x 20 cm<sup>2</sup> each)
  - Trigger position : 30, 60 and 90 cm
  - Measured drift field points: 115, 125 and 135 V/cm







### **RAON** Neutron Detector Array (NDA): Structure





#### **RAON** NDA: Performance test with prototype





- Production reaction:  $p+^{7}Li \rightarrow n + ^{7}Be$
- Neutron beam flux:  $1 \times 10^{10} \text{ n/sr}/\mu\text{C}$
- Neutron energy: 65 and 392 MeV
- Background neutrons above 3 MeV is < 1%</p> [NIMA 629, 43 (2011)]



- Significant energy-loss effect in the Li target at 65 MeV
- Low-energy background dominated by the 3-body decays  $^{7}\text{Li}(p, n^{3}\text{He})$   $^{4}\text{He}$
- Energy resolution (FWHM): 3.1% @ 392 MeV, 1.3% @ 65 MeV

### **RAON** NDA: Performance with prototype





← Position difference between the projected hit position and the detected hit position for cosmic muons:  $\Delta x_4 \equiv x_{D4,proj} - x_{D4,hit}$ ← Relative position resolution for cosmic muons for one bar:  $\sigma_x = \frac{\sigma(\Delta x_4)}{1.87} = 2.0 \text{ cm}$ :  $R_x(\mu) = 4.8 \text{ cm}$  (FWHM)

→ Hit position difference between neighboring scintillators for neutrons with simultaneous hits: Δx<sub>S1</sub> ≡ x<sub>D1</sub> - x<sub>D2</sub> for 10 MeV threshold and δt < 3 ns</li>
 → Relative position resolution for neutrons for one bar:

$$\sigma_n = \frac{\sigma(\Delta x_{S1})}{\sqrt{2}} = 4.5 \text{ cm}: R_{\chi}(n) = 7.5 \text{ cm} (FWHM)$$



Comparison of performances by cosmic rays for similar configuration of neutron detectors [NIMA 927, 280 (2019)]

	LAMPS (this work)	MoNA [13]	NEBULAR [14]	LAND [15]
Dimensions (cm <sup>3</sup> )	$10 \times 10 \times 200$	10  imes 10  imes 200	12  imes 12  imes 180	$10 \times 10 \times 200$
Time resolution (ps)	309	423	376	588
Position resolution (cm)	4.8	5.2	6.1	7.1

13 October 2022

### **RAON NDA: Construction**

- RISP
- Installation of all modules in the frame was completed at the Sejong campus of Korea University in Dec. 2018 to test the performance.
- The whole system was dissembled and transported to the RAON site in Sindong in March and assembled again with the three additional veto walls in September in 2022.
- The fully assembled system will take the cosmic muon data at the RAON site very soon.







ToF & Trigger array (BTOF/FTOF)

BDC (left) & SC (right) in beam diagnostic vacuum chamber







# Status of beam commissioning and summary



### **CAON** Preparation of RIB production by ISOL



• Target Ion Source: Sn beam extraction using RILIS and transportation to A/q separator (Apr. 2022)



Nuclei	<sup>116</sup> Sn	<sup>117</sup> Sn	<sup>118</sup> Sn	<sup>119</sup> Sn	<sup>120</sup> Sn	<sup>122</sup> Sn	<sup>124</sup> Sn
Measured Current (nA)	0.243	0.152	0.360	0.161	0.450	0.097	0.102
Current Ratio (%)	15.5	9.70	23.0	10.28	28.75	6.20	6.52
Natural abundance (%)	14.54	7.68	24.22	8.59	32.58	4.63	5.79
Abundance ratio	14.79	7.83	24.71	8.76	33.23	6.32	6.65



- RI beam commissioning plan for ISOL with SiC target
  - <sup>24</sup>Na beams with an intensity of ~10<sup>6-8</sup> pps (1 kW@70 MeV) in Oct.~Dec. 2022
  - <sup>24-26m</sup>Al beams produced and transported to Ultra lowenergy Expt. hall (MMS & CLS) in 2023
  - Plan to provide <sup>20-24</sup>Na, <sup>22-23</sup>Mg, <sup>24-26</sup>Al and <sup>8-9</sup>Li beams
- $\bigcirc$  UC<sub>x</sub> target from 2025
- ← Beam current ratio can be explained by the natural abundance of Sn.

### **RAON** KoBRA beam commissioning plan





● KoBRA beam commissioning in Mar. – Jun. 2023

- RI production using quasi projectile-like fragmentation from <sup>40</sup>Ar in the energy range of 20~30 MeV/u
- $B\rho$ -ToF- $\Delta E$  method for PID with detectors at F0~F3



## **RAON** Summary

- Major achievements
  - SCL3: Installation completed in 2021
  - Cryogenic plants: Cooldown and RF conditioning, beam commission started in Sep. 2022
  - ISOL: SIB transportation for all sub systems and beam lines tested in Dec. 2021
  - KoBRA: Machine commissioning done in Oct. 2021
- Near-term plan (for the next  $\sim$ 2 years)
  - Delivery of stable <sup>16</sup>O & <sup>40</sup>Ar beams to KoBRA in 2023
  - Extraction of RIB from ISOL and delivery to ultra low-energy experimental hall for MMS & CLS in 2023
  - KoBRA beam commissioning experiment with RIBs for  $A \leq 50$  with beam energy  $\leq 20$  MeV/u in 2023
  - Installation and independent commissioning of IF, LAMPS, BIS and μSR in 2023
  - Preparation of the 2<sup>nd</sup> phase for the construction of SCL2 by 2024
- Long-term plan
  - Operation of ISOL with UC<sub>x</sub> target from 2025
  - Completion of SCL2 and stable operation of U beams at 200 MeV/u up to 80 kW (Goal: 400 kW)
  - Starting of the scientific program with ISOL and IF
  - Beam commissioning for ISOL  $\rightarrow$  SCL3  $\rightarrow$  SCL2  $\rightarrow$  IF





## Thank you very much for your attention!